BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer(Ele),BBMP, Dasarahalli Zone.Hesaragatta main Road,Bagalagunte, B'lore-73

Tender Notification No:EE/ELE/DZ/TND/04/ 2020-21, Datd:- 27-01-2021

Item No. 01

SCHEDULE -B

Name of Work: Annual Maintenance of Street Lights Package D-2 ward No 13 Mallasandra

Sl. No.	Description of work	Unit	Quantity	Rates Quoted by Contractor VICTORY ELECTRICAL	
				Rate in Figure	Rate in words
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. i) Poles with 36/40 W fluorescent tube light street lighting system.	Each	148.00	468.51	Four Hundred sixty eight and fifty one paise only
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 125 W MV light Park lighting system.	Each	89.00	516.92	Five Hundred sixten and Nintey two paise only
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 250W HPSV light street lighting system.	Each	1323.00	696.77	Six Hundred nintey six and seventy seven paise only
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 400 watts HPSV light street lighting system.	Each	58.00	764.21	Seven Hundred sixty four and twontey one paise only
5	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 24 W LED light street lighting system.	Each	80.00	601.49	Six Hundred One and fourtey nin paise only

J. Jay dev

Scanned by CamScanner

6	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 65 W LED light street lighting system.	Ench	184.00	784.27	Seven Hundred eightyfour and twenty seven paise only
7	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. Poles with 90 W LED light street lighting system.	Each	134.00	941.63	NIN Hundred fourtey one and sixtey three paise only
8	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut-outs, wiring connector and M.S. Box with proper insulation etc , complete.	Each	15.00	2129.4	Two Thusand one Hundred twontey nin and four paise only
9	B. Work to be carried out as per requirement & actuals and as per the direction of the in charge engineer, Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/looting of the pole.a)5 mtr pole	Each	89.00	375.93	Three Hundred seventey five and ninety thrre paise only
10	c) 8 Mtr and above street light pole	Each	12.00	526.3	Five Hundred twontey six and three paise only
11	Moulded Case Circuit Breaker (MCCB) Three Pole 100Amps 25kA	Each	33.00	1857.75	One Thusand eight Hundred fiftey seven and seventey five paise only
12	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Each	33.00	1488.66	One Thusand four Hundred eightey eight and sixtey six paise only
13	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP A 2 X 25 + 1 X 25 SQ MM	Mtrs	1000.00	97.74	Nintey seven and seventey four paise only

Executive Engineer(Ele)
Dasarahalli Zone
BBMP Bangalore-73

I Agree to carry out this work at 31.6498 % Below the Rates mentioned in the Schedule-B.

Signature of the Contractor

Scanned by CamScanner